443

BANGALORE DIVISION.

Dated 20th August 1931.

1. Notice is hereby given that sealed tenders will be received at the Office of the Executive Engineer, Bangalore Division up to 15th September 1931, for constructing a Middle School Building, Fort Bangalore. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of June 1932.

2. The plans, detailed estimates and conditions may be seen at the Executive Engineer's Office at Bangalore between the hours of 11 A.M. to 5 P.M.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of Rs. 500 (five hundred) in cash or Government Promissory Notes as earnest money, and be superscribed "Tender for constructing a Middle School Building at Fort, Bangalore" in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Executive Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance, of the tender the successful competitor will be required to execute the usual contract bond, in default of which his tender will be considered cancelled and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the notice board in the Executive Engineer's Office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

9. Percentage rates above or below the estimate amount will not be accepted.

10. No claims for enhanced rates will be entertained on any account after acceptance of tenders.

11 The contractor will be dealt with in terms of the bond for any short progress or delay. In matters of all disputes about rates measurements quality of work, etc., and in all disputes of any kind the decision of the Chief Engineer will be final and legally binding on the contractors.

12. Rates should be quoted both in words and figures for each item of work and lumpsum provisions are subject to modifications as per data worked out during the execution. For individual items of work under lumpsum provisions the rates tendered for similar items of work will be paid and for other items the rates as per schedule of rates will be paid at the discretion of the Executive Engineer.

13. Rates for masonary include bond stones to the required percentage at the required intervals of the quality and size to be specified.

Abstract of quantities.

No.	Items of work	Unit	Rate	Quantity	Remarks
1	Earthwork, excavation for foundation and filling in basement watering and consolidating.	C.yd.	...	270	
2	Filling foundation with stone jelly concrete in chuna with 6" layers watering and tamping,	C.ft.	...	1,760	
3	Filling foundation and basement with burnt size stone in clay including bond slabs ever 6' apart, complete.	,,	...	6,288	
4	Superstructure with burnt brick in clay with bond slabs at 6' apart in length and 3' in height.	,,	...	8,201	
5	Superstructure in burnt bricks in mortar	,,	...	1,753	
6	Arch work in burnt bricks in mortar	,,	...	43	
7	Burnt stone slabs 6" thick rughly dressed and fixed ...	S.ft.	...	1,044	
8	Burnt stone slabs 6" thick dressed and fixed over dwarf walls with edges chamfered.	,,	...	80	
9	Burnt stone slab posts 1' wide and 6" thick and notches cut and fixed.	,,	...	330	
10	T. W. doors with frames $3\frac{1}{2}" \times 4\frac{1}{2}"$ with $\frac{1}{2}$ panalled and $\frac{1}{2}$ glazed shutters $1\frac{1}{4}"$ thick complete with hinges, hooks, etc.	,,	...	114	

No.	Items of work	Unit	Rate	Quantity	Remarks
11	T. W. windows with frames 3½″ x 4½″ with ½ panalled and ½ glazed shutters outside with iron bars, hooks, etc., complete.	S.ft.	Rs.	205	
12	Cement concrete perforated ventilators as per design.	,,		214	
13	T. W. wrought and put up including wood oiling.	C.ft.		467·60	
14	Roofing with first class Mangalore tiles on teak reepers 2″ x 1″ etc., complete.	Sqr.		91·72	
15	Mangalore ridge tiles set in mortor ...	R.ft.		304	
16	Providing gutters with zinc sheet 3′ with T.W. planks, etc., complete.	S.ft.		198	
17	T. W. Eaves board 9″ x 1″ plain ...	R.ft.		688	
18	Chunam plastering	Sqr.		173·50	
19	White and colour washing two coats ...	,,		173·50	
20	Flooring with Mangalore square tiles on 3″ concrete bed and cement pointing.	,,		37·50	
21	Flooring with Kadappa slabs on 3″ concrete bed and cement pointing.	,,		15·86	
22	Masonry dwarf wall on slabs with plastering complete.	R.ft.		397	
23	Chocolate painting to doors, etc., two coats ...	Sqr.		5·51	
24	T. W. finial at ridge	Each		8	
25	Cement pointing to basement	Sqr.		12·00	
26	Coping over compound wall with brick in clay and chunam plastering and white washing, complete.	R.ft.		42	
27	Do do to gate pillars	Each		6	
28	Masonry borders to ventilators 6″ x 1″ ...	R.ft.		400	
29	Providing T. W. gate with iron fittings, complete.	S.ft.		24	

N. G. KRISHNA IYENGAR,
Executive Engineer.

GOVERNMENT OF MYSORE, ELECTRICAL DEPARTMENT.

Abstract Notification dated 10th August 1931.

Attention of the public is invited to the detailed notification, dated the 31st July 1931, calling for tenders for constructing the Staff Quarters at Mysore, published in Part VI, pages 870 to 871 of the *Mysore Gazette*, dated 13th August 1931.

The latest date for receiving tenders is 2 P.M., on 29th August 1931.

Notification dated 11th August 1931.

Notice is hereby given that sealed tenders will be received at the Office of the Chief Electrical Engineer, Bangalore, up to 2 P.M., on 7th September 1931, for constructing a block of Senior Operators' Quarters at Kolar Town.

1. The tenders will be opened in public at 2 P.M., on 7th September 1931. The work should be completed within three months and the monthly progress be not less than Rs. 1,000.